



Typical elevation of a Vertical Slider.



Section through the Vertical Slider.



Vertical Slider Jamb detail.

Specification:

Aluminium sections are to be extruded from 6060 alloy EN755-2.
 EP White Gloss - 60 Micron finish.
 All aluminium to be powder coated to BS 6496.
 Frames and sashes are to be mechanically jointed using BZP screws to DIN 7982 - 8 microns.
 The sub-frame is from English hardwood, kiln dried to KD:FAS1F.
 Sub-frames are butt jointed using BZP screws to DIN 965 - 8 microns. Standard sizes 45mm x 21mm & 62mm x 21mm.
 Non-standard sizes are available to order.
 All frames are factory glazed.
 A choice of 4mm or 6mm clear float annealed or toughened.
 6.4mm clear laminate or 6.4mm Acoustic Glass.
 Gaskets are in accordance with BS 2782 in a standard colour of BLACK.
 All sash polypropylene woolpiles are to BS 7386.
 All frames include upvc or timber trim

Revision:

Drg. No.	VS RF	Scale:	1:20 & 1:2 (at A4)	Protech Direct (www.secondaryglazing.com) Blue Bridge Centre Horndale Avenue Newton Aycliffe Durham DL5 6DS tel: 01325 310520
Client:		Drawn by:		
Architect:		Date:		
Contract:	Standard Vertical Slider details. Reveal Fix.			